

Protective fencing

To be erected prior to the commencement of all works on site, and retained in place throughout construction.

Default specification: To comprise either 2.4m wooden site hoarding or a 2.3m high scaffolding framework comprising of vertical and horizontal framework, well braced to resist impacts, with uprights to be spaced at a maximum of 3.0m intervals and driven into the ground by a minimum of 600mm. On to this, standard anti-climb welded mesh panels are to be securely fixed to each other with at least two scaffold clamps and to the scaffold framework with wire.

Secondary Specification: To comprise of 2m tall welded mesh panels on rubber or concrete feet. Panels are to be joined together using a minimum of two anti-rattle couplers, installed so that they can only be removed from inside the fence. The panels should be supported on the inner side by stabiliser struts, which should also be attached to a base plate and secured with ground pins.

All weather notices should be erected at regular intervals on the welded mesh panels with words such as "Construction exclusion zone - Keep out".

Ground boarding

New temporary ground protection should be capable of supporting any traffic entering or using the site without being distorted or causing compaction of underlying soil.

Note The ground protection might comprise one of the following:

a) for pedestrian movements only, a single thickness of scaffold boards placed either on top of a driven scaffold frame, or to form a suspended walkway, or on top of a compression-resistant layer (e.g. 100mm depth of woodchip), laid onto a geotextile membrane;

b) for pedestrian-operated plant up to a gross weight of 2t, proprietary tree-ripped ground protection boards placed on top of a compression-resistant layer (e.g. 150mm depth of woodchip), laid onto a geotextile membrane;

c) for wheeled or tracked construction traffic exceeding 2 t gross weight, an alternative system (e.g. proprietary system or pre-cast reinforced concrete slabs) to an engineering specification designed in conjunction with arboricultural advice, to accommodate the likely loading to which it will be subjected.

For situations other than those described in a) or b), the ground boarding is to be designed by a suitably qualified person to an engineering specification in conjunction with arboricultural advice, to be able to support the expected loading to be placed upon it.

In all cases, the objective of the ground boarding is to avoid compaction of the soil beneath, as that tree root function remains unimpaired.

Supervised demolition

Hard surfacing:

Removal of and/or replacement of hard surfacing situated either partially or completely within the RPA's of retained trees shall be undertaken with care and under the direct on-site arboricultural supervision as these areas are likely to contain roots.

Where this is necessary the wearing course will be broken up using a hand held pneumatic breaker, hand tools and a wheel barrow to break up and remove the surfacing. If it is necessary to remove the sub base this is to be undertaken using hand tools such as a fork to loosen the material and removed using shovel and wheel barrows.

In some situations and at the discretion of the arborist it may be possible to use an excavator using a hydraulic breaker and suitably sized toothless grading bucket. If an excavator is to be used it must be situated outside of the RPA's or from ground boarding.

Which ever system is used there is to be NO disturbance of the soil beneath. If roots are found they are to be covered over with damp hessian and a layer of either sharp sand, wood chip or top soil to prevent desiccation.

Structures:

Demolition of existing structures and foundations situated either partially or completely within RPA's of retained trees shall be undertaken with care and under the direct on-site arboricultural supervision as these areas are likely to contain roots.

Where it is necessary for the foundations to be removed they are to only be removed where critical to the proposed development and to the minimum depth required. The foundations will be broken up using a hand held pneumatic breaker, hand tools and a wheel barrow to break up and remove the surfacing. In some situations and at the discretion of the arborist it may be possible to use an excavator using a hydraulic breaker and suitably sized toothless grading bucket. If an excavator is to be used it must be situated outside of the RPA's, on top of the hard surfacing working away from the RPA's or from ground boarding.

Which ever system is used there is to be NO disturbance of the soil on the tree side of the foundations. If roots are found they are to be covered over with damp hessian and a layer of either sharp sand, wood chip or top soil to prevent desiccation.

Supervised Excavation

All excavations within and immediately adjacent to RPA's are to be undertaken under direct on-site arboricultural supervision.

Any roots that are to be cut will be clearly severed by the project arboriculturist using a suitable hand saw or secateurs. The edge of all excavation closest to the retained trees will be covered over with damp hessian to prevent drying out, and where necessary be shrouded to prevent soil collapse or contamination by concrete.

If appropriate soil beneath the depth of the excavation may be sheet piled, regular piled or have individual piles installed.

Manual excavation:

Excavations within the RPA's will be initially undertaken by hand under direct on-site arboricultural supervision to a minimum of 600mm deep to be confirmed by the project arboriculturist, whether this is for proposed foundations, hard surfacing or underground services. The soil is to be loosened with the use of a fork or pick and/or air-spade and then cleared with a shovel and/or the aid of an air-spade and air-vac.

Mechanical excavation:

Excavation within the RPA's will consist of a mixture of mechanical and manual excavation.

Where an excavator is used it will be fitted with a suitably sized toothless grading bucket, using a grading /scrapping motion rather than digging. During each motion the excavator will not be permitted to remove more than 10 -20mm deep of soil in any one pass.

If any roots are discovered, mechanical excavation will immediately be stopped and manual excavation will take over to expose the root. Upon the root being uncovered and either severed or protected the excavations can then continue.

Any excavator or other machinery that is to be used will be situated outside of the RPA's of all retained trees or on top of a suitable ground protection.

Where an excavator or any other machinery is to be used within RPA's or beneath canopies the project arboriculturist will clearly instruct the operator about what they want and expect to happen prior to any works may commence.

Arboricultural Supervision

The arboricultural consultant will be required to attend site to directly supervise all demolition and construction works that have to be undertaken within the root protection area. This will include:

1. Pre-commencement site meeting.


2. Location of protective measures.

3. Supervised demolition within and adjacent to RPA's of tree numbers G3.

4. Supervised excavations for foundations within and adjacent to the RPA's of tree numbers 2 and G5.

5. Any demolition and/or excavations within or adjacent to RPA's, including foundations, hard surfacing or underground services (a non-exhaustive list).

6. Arboricultural sign off and removal of protective measures.




Tree Work Schedule			
No.	Species	Works	Category
3	Maple	Fell to ground level, grind out stump	C
11	Ash	Fell to ground level	U
12	Plum	Fell to ground level	U
G1	Various	Partial removal - Fell to ground level, grind out stump	C
G5	Various	Crown reduce W canopy to boundary	C

All tree work is to be undertaken in accordance with British Standard BS 3998:2010 Tree work - Recommendations.

All existing trees to be removed and the site is to be left as found.

Care is to be taken of the ground around retained trees to make sure that it does not become compacted as a result of tree surgery operations. No equipment or vehicles such as timber lorries, tractors, excavators or cranes shall be parked or driven beneath the crowns of any retained trees, to prevent subsequent compaction and root death.



Key:

Tree No.:

1 Tree Canopies

Category 'U' trees

Category 'C' trees

Category 'C' groups

Arboricultural Supervision/Excavations

Trunks

Category 'A' groups

Category 'C' trees

Existing Site (GS) line

Arboricultural Supervision/Excavations

Protective fencing

Ground boarding

Arboricultural Supervision/Excavations